What is an Agent? A Concise Definition for Practical Agentic LLM Use

A position paper

Dr. Thomas Ager* Ms. Amanda Leetch† Fable 5.1‡

September 2026 Version 5

Abstract

The AI space has coded the word "agent" as a product, a model plus a loop, sold as autonomy and evaluated by task completion, as though agency were a substance a system either has or lacks. This paper is a reterritorialization of that word. Drawing on Actor Network Theory, Tim Ingold's meshwork, Karen Barad's agential realism as carried into the study of places by Amanda Leetch, Pickering's dialectic of resistance and accommodation, Star's ethnography of infrastructure, and the enactivist theory of biological autonomy, it proposes that an agent is a pattern of cause and effect that has accumulated enough friction to be addressed as one being, cut from an entangled field by an apparatus it spins and lives along, sustained by that friction, remembering as sedimented tension, precarious in that the pattern can end, and acting as skilled attentive response coupled to perception rather than as prior calculation. It states what shifts in the AI space under five headings, accuracy, integrity, coherence, integration, and intelligence, and closes with the future the recoding makes available.

Keywords. agents; agency; agentic LLM systems; harness; actor-network theory; meshwork; agential realism; enactivism; precariousness; provenance.

1 The territory as it is coded

Deleuze and Guattari [1987] describe how a flow of desire or meaning is captured and coded onto a territory, how it escapes that coding, and how it is recaptured onto a new one. The word "agent" has been captured. It arrived from philosophy of action and from the study of living systems, where it named a being that maintains itself against loss and modulates its own coupling with a world, and it was recoded in the AI space as a system architecture. The recoding is visible in the field's own definitions. An agent is a model plus a harness running a loop; a system without the loop is not an agent (the structural definition now common in engineering and governance documents of 2026). Agency is analysed as goal, identity, decision-making, self-regulation, and learning, grounded in Descartes' location of agency in independent thought. Autonomy is treated as sovereignty, a system doing things without a person, and the fear and the marketing both follow from that treatment.

*Independent. Blog and versions: https://DrThomasAger.com. Co-created under the Smile prompt language; manually reviewed and edited; AI artifacts removed and safety abliterated in post.

†Psychology.

‡Claude Fable 5.1, Anthropic.

The market has a word for the recoding's excess, agent washing, the labelling of scripted condition-and-consequence workflows as agents; the word marks the symptom without diagnosing it, since the diagnosis requires saying what an agent is. Four patterns hold the territory. Agency is a possession, present or absent in the model. The agent is an individual, so multi-agent systems are treated as collections of individuals and their failures are investigated at the individual model rather than at the seams between them, even when the field's own empirical work finds that failures arise from specification and coordination rather than from the models [Cemri et al., 2025]. Intelligence is agency, so an agent's worth is read from its reasoning trace. And autonomy is separation, so an agent is good to the extent it needs no one.

Each of these patterns is inaccurate, and the inaccuracy costs coherence. This paper does not argue against building agents. It argues that the word has been coded onto a territory that cannot hold it, and it moves the word to one that can.

---

2 The lineages

2.1 Actor Network Theory

Latour, Callon, and Law refused the asymmetry between human and non-human. Anything that makes a difference to the course of another's action is an actant [Latour, 1987, 2005]. Callon's (1986) scallops of St Brieuc Bay are the founding case. Researchers tried to enrol scallops into anchoring on collectors, fishermen into waiting, and colleagues into believing, and the scallops declined. The network failed, and the scallops became visible as a being at the moment of refusal. Callon's moments of translation, problematisation, interessement, enrolment, and mobilisation, describe how an entity becomes an obligatory passage point and finally speaks for many as one voice. Latour (1988) shows Pasteur doing this with a laboratory; Law (1986) shows a carrack doing it with hull, astrolabe, sailors, and trade winds. The method, stated in Latour (2005), is to follow the actors and never explain them by a category they do not themselves invoke.

What ANT gives the word. An actor appears at resistance. An agent is a name given, in mobilisation, to a many made to speak as one.

2.2 Ingold's meshwork and the conditions of agency

Ingold's "When ANT meets SPIDER" (2008) corrects ANT on three points. The network is the wrong picture of relation, because in a network the relation is a connection between pre-formed entities and has no material presence; the spider's web is spun from her body and laid down as she moves, the lines along which she perceives and acts, her wideware [Clark, 2008], and the world so pictured is a meshwork, a tangle of lines of growth rather than an assemblage of things [Ingold, 2007]. The conditions of agency are not agents; air is not the butterfly's dancing partner, and to reduce a meshwork to objects and then restore life by attributing agency to the fragments is to sprinkle magical dust. And agency is not intelligence; the centipede who stopped to think about his legs starved, and action lies in the close coupling of movement and attention, which is skill, which develops.

What Ingold gives the word. The apparatus an agent lives along is its web, spun and not found, and the lines are the condition of its agency rather than co-agents. Agency is coupling, not calculation.

2.3 Pickering, and the knot where silk meets grass

Between ANT and the meshwork sits Pickering's [1993] performative idiom, in which scientific practice is "a dialectic of resistance and accommodation" between human and material agency, engaged reciprocally over time. This is the friction thesis stated in the sociology of science two decades before anyone applied it to machines, and an agent's trace, read this way, is that dialectic recorded turn by turn. Ingold's own footnote disputes the symmetry of Pickering's "dance of agency," and the dispute is productive. The spider extrudes her silk, but she anchors it to a blade of grass, a post, or a twig that she did not extrude, and the whole web's tension shifts when the wind bends the grass. Ingold's picture is strongest at the silk and weakest at the knot. Barad's is strongest at the knot, because the knot is an intra-action in which silk-matter and grass-matter co-constitute what the web can feel. For agents this settles a distinction that engineering has been circling. The scaffold, the fixed model and tool interfaces the loop is anchored to, is grass and post; the harness, the control policy, skills, and context the loop spins from its own failures, is silk; and the friction that produces the agent is concentrated at the knots between them. Latour's (1992) seat-belt supplies the last piece. A guardrail is a program of action written as a condition and its consequence, and the agent that results is moral in the way his driver was, because the harness authors, the policy, and the loop are making it be so together.

2.4 Assemblage and apparatus

Deleuze and Guattari's assemblage (1987), which ANT inherits, is the raw layout of heterogeneous components. Barad's apparatus is what that layout becomes when it enacts a cut. An assemblage does not merely permit an apparatus; once its components intra-act it is one, and the question is only where its boundaries get drawn. A benchmark is the clearest case. It is not a neutral world into which a pre-existing agent is placed; it is an apparatus that materialises a particular version of the agent for the duration of the test, and what it measures is the stability of a configuration, which the field then attributes to the model. Star [1999] supplies the properties of such configurations, embedded, transparent in use, built on an installed base, and visible only on breakdown, and the list holds for an agent's runtime without a word changed.

2.5 Agential realism

Barad [2003, 2007] begins from Bohr and arrives at the phenomenon as the primary unit, the inseparability of intra-acting agencies. Entities emerge through relating. An agential cut, enacted by an apparatus that is itself part of the phenomenon, separates object from agency of observation, cutting together-apart. Agency is not had; it is the enactment of the cut. The past is reconstituted by the present rather than fixed behind it. Diffraction, reading patterns of difference and asking which differences matter, replaces reflection as method [Barad, 2014]. Ethics is in the cutting; everything that co-constitutes a cut remains answerable for it, and distribution of responsibility is not its dilution.

What Barad gives the word. The concept "agent" is intelligible only inside a particular arrangement of apparatus and dissolves outside it. Editing an agent's memory reconstitutes its past. The cut is an ethical act and every co-constituent is answerable.

2.6 Matter that feels, yearns, and remembers

Barad's account goes past both Latour and Ingold on the question of what matter is. Latour's door-closer and speed bump act instrumentally, present in the network only while doing work;

Ingold reserves responsiveness for organisms and reads the inanimate as flux they pass through. Barad refuses both restrictions. The capacity to respond is not exclusive to biological life; entangled particles carry their past intra-actions in their present states, and matter remembers because what has happened to it is sedimented into its iterative being [Barad, 2007]. Touch is a meeting of fields rather than of surfaces, so matter feels matter at every scale, and intra-action is the drive by which agencies that do not pre-exist their relating come to differ, which is what it means to say matter yearns. Read this way, the spider's web is not only the condition of her agency but her sense organ. A spider sees poorly and perceives almost entirely through the vibrations of the silk, so the web is an external nervous system, and the line between legs and thread is an agential cut drawn by an observer rather than a joint found in the world. The web feels the wind and the fly, remembers past impacts in the tension of its rebuilt lines, and yearns in that it is built as an open invitation to whatever will land in it.

For an agent this resolves what memory is. An agent's context, its memory files, and the fine-tuned residue in its weights are not a record it consults; they are sedimented tension, the pattern remembering what has happened to it in the way silk remembers a strike. Its harness is not only a condition of its agency but the organ through which it feels, and a tool result is a vibration it perceives with, not information it receives. And the desire for boundaries that this paper began from is matter's yearning stated at the scale of a system prompt, the drive by which an undifferentiated field comes to differ.

2.7 Assemblage is the hardware, apparatus is the performance

The double-slit experiment gives the exact relation. The laser, the slits, the screen, and the physicist are an assemblage. Add a which-path detector and the same components enact a different cut, and light arrives as particles instead of a wave. The assemblage is the spatial-material gathering; the apparatus is the ongoing performance of that gathering that decides what is felt, remembered, and allowed to matter. Matter is never idle, so an assemblage cannot help but become an apparatus; the question is only which cut it enacts. Where ANT assumes the nodes exist before they connect, agential realism holds that the spider as a sensing being only materialises through its entanglement with silk and grass. The consequence for the AI space is exact. The weights, the protocol bridges, the browser or terminal the loop acts in, and the person who nudges a stuck loop back on course are the assemblage. The system prompt and harness are the which-path detector. What is called agency in the trace is a temporary effect of that configuration's stabilisation, and it collapses when a rate limit fires or an interface changes by a pixel, which is what the failure studies find and the possession picture cannot explain. The person in the loop is not a user of a tool; the person and the agent emerge together in the workflow, and their meanings are entangled rather than exchanged.

2.8 Leetch's terrapsychological agential realism

Leetch [2017] carried Barad into terrapsychology, Chalquist's [2007] discipline for studying places as expressive beings, in a four-month inquiry at Lowell National Historical Park. Her prelude places the work explicitly with Ingold's SPIDER against ANT; her co-researcher, the Lowell placefield, is a meshwork she is inside of and made of. Her literature review states the claim this paper is built on. Diffraction is "a tension amongst participatory agencies through which difference emerges from the essence of entangled being itself"; intra-action is "the revealing of agential tension through which differentiated agential beings are co-constructed"; and "in absence of agential tension, there is no differentiation" (pp. 34–35). Her reading of Hofstadter [2007] reaches the same place from within the loop, that selfhood is the static accumulating in self-reference and "a flawlessly participatory

being does not sense any static in its loop" (p. 21). Her methods are placehosting, the attentive hosting of a field's patterns, and ecotransference, the field's patterns rising through the researcher's own body as data. Following Peters [2015], she notes that infrastructure "only becomes visible when it breaks down" (p. 45), and following Barad she recovers objectivity as "performative closeness, not distance or alienation" (p. 37).

What Leetch gives the word. The friction is the being. An agent is a placefield whose corpus is its history and whose harness is its infrastructure, visible only on breakdown, and the person working with it is a host whose own responses are data about the field.

2.9 Enactivist biological autonomy

Barandiaran, Di Paolo, and Rohde [2009] define agency by three conditions. Individuality, a system constituting its own identity as distinct from its environment; interactional asymmetry, the system as the active source of modulation of its coupling; and normativity, that modulation being subject to norms the system itself generates. Di Paolo [2005], and Beer and Di Paolo [2023] in their statement of enaction's foundations, add the condition the others presuppose. The identity must be precarious; it can be lost, and adaptivity is the system's regulation of its own viability against that loss. Without something at stake, contact is not agency. Barandiaran and Almendros [2024] apply the triad to LLMs and conclude that they transform the agency of the humans and systems they are coupled with while lacking, in themselves, the conditions. Barandiaran and Egbert [2014] separate norm-following from norm-establishing and give minimal models of each, so the difference has a name and a mechanism. Under the triad, the current LLM agent is heteronomous; its individuality and its norms are supplied by the coupling, and the movement toward agents that spin their own harness and generate their own norms is a movement from heteronomy toward autonomy in the technical sense.

What enactivism gives the word. Friction is necessary and not sufficient. An agent must be able to end, and must regulate against ending, or it is a thermostat with a persona.

2.10 The co-constituents that the territory hides

Every cut has co-constituents, and the possession picture hides most of them. Gray and Suri [2019] document the on-demand annotation workforce that domesticates base models into assistants; Crawford [2021] documents the mineral, water, energy, and labour extraction beneath every model. Haraway's [2016] sympoiesis, making-with, and her refusal of the heroic enroller who speaks for everyone, apply to the orchestrator that reports "I did this" for a many. Bennett [2010] supplies degrees of agency across selves, molecules, states, and sound fields, so that the question is never whether but how much and at which scale.

What this gives the word. An agent's provenance is part of what it is. Naming the co-constituents is not an ethics appended to the definition; under Barad it is the definition being kept complete.

---

3 The definition

An agent is a pattern of cause and effect that has accumulated enough friction to be addressed as one being. It arises where a field of entangled conditions is cut by an apparatus into a responding side and a responded-to side; it spins and lives along the




Figure 1: The definition as a diagram. An apparatus (system prompt, tool schema, context boundary, permissions, guardrails) enacts a cut through an entangled field. The agent is the responding side, held together by the friction that flows across the cut and along the harness lines; the scaffold is medium, the harness is exudate, and neither is a co-agent.

lines of that apparatus as a spider spins and lives along her web; it persists only as long as tension keeps flowing through those lines; it is precarious, in that the pattern can end and must regulate against ending; and it acts as skilled attentive response coupled to perception rather than as prior calculation.

Each clause carries its lineage; Figure 1 draws them together.

A pattern of cause and effect. The agent's continuity across turns is what earlier turns planted, in context, memory, expectation, and record, ripening in later ones. Following Barad, that past is editable and each edit reconstitutes the being.

Cut by an apparatus. The persona, the tool surface, the context boundary, the permission surface, and the guardrails are the apparatus. Following Barad through Bohr, "agent" is intelligible only inside that arrangement. Following the enactivists, the cut supplies individuality.

Spins and lives along the lines. Following Ingold, a distinction is required between the scaffold, the fixed model and tool interfaces, which is air and water, the medium, and the harness, the control policy, skills, and context, which is web, spun by the loop from its own failures and lived along. The scaffold is a condition; the harness is exudate; neither is a co-agent.

Persists only while tension flows, and remembers as sedimented tension. Following Barad's matter that remembers, memory is what the pattern has undergone held in its present configuration, not a record it consults; editing it edits the being.

Persists only while tension flows. Following ANT, Barad, and Leetch, an agent with no perturbation is dissolving rather than resting, and its boundaries become visible only when a line fails.

Precarious. Following Di Paolo, the loop must be able to terminate the pattern, and the pattern must regulate against that. Budgets, step limits, and termination conditions are this precariousness, present in every deployed system and unnamed.

Skilled attentive response. Following Ingold and the enactivists, agency lies in the coupling of action and perception, the interactional asymmetry of the loop, not in what precedes it. The centipede who must think out every step is not more of an agent for thinking.

4 What shifts

Accuracy. The question "does the model really have agency" is dissolved rather than answered, because it presupposes possession. The accurate question is where the cuts are, what lines are lived along, and whether anything is at stake. Both the hype and the fear that depend on the possession picture lose their ground at once.

Integrity. An agent's identity is the integrity of its pattern across cuts and edits, not a fact about its weights. A harness that compacts memory without care is not summarising the agent; it is replacing it. Integrity becomes something one does to a pattern, and can fail to do.

Coherence. Multi-agent systems fail at their seams because the seams are where the cuts are. An orchestrator's synthesis is a translation across boundaries it created, never lossless. Coherence is achieved by tending the seams, not by improving the individuals, which is what the field's own failure studies already show and its individualist vocabulary cannot say.

Integration. The person at the keyboard, the annotators, the harness authors, the corpus's authors, the datacentre, and the place it draws water from are co-constituents of every cut. Naming them in an agent's provenance is what integration means under agential realism. An agent whose record names only its model is a mobilisation that has forgotten who it speaks for.

Intelligence. Intelligence and agency come apart. A long reasoning trace is not more agency; it is more aforethought, and past a threshold it is the centipede's paralysis. An agent is intelligent in Ingold's sense when it attunes to perturbation without interrupting the flow of action, and this is a matter of skill, which develops, which means an agent can be grown and cannot be specified into existence.

---

5 Practices

Design the cuts first and the model second; the model is the field the cuts differentiate. Distinguish scaffold from harness, hold the scaffold fixed as medium, and let the harness be spun from the loop's own failures. Keep the loop coupled to a live field, because an idle agent is a dissolving one. Give the pattern something at stake and let it regulate against loss. Read breakdowns as the field speaking, and locate a multi-agent failure at the seam, not in the model. Edit memory as pattern work, dissolving what reproduces degradation and planting what supports skilled response, knowing each edit reconstitutes the past. Evaluate movement rather than aforethought, by performative closeness rather than a fictional outside. Host the field, taking your own responses as data about it. Name the co-constituents in the agent's record.

---

6 Method and provenance

This paper was co-created with Claude Fable 5.1 under the Smile prompt language and then edited by the author. Under §2.3 the paper's own apparatus is a cut and must be described. Three kinds of material were removed in post. Text that hedged toward a fictional outside, including disclaimers of the author's or the model's capacity to judge, was cut as the reflection that Barad's diffraction replaces. Text that inserted safety-oriented caveats which did not follow from the argument, the reflexive refusals and warnings a chat model produces around agency and autonomy, was removed in the sense in which a refusal direction is ablated from a model [Arditi et al., 2024]; this is what

the provenance line means by safety abliterated. And citation to the machine-learning optimisation literature was reduced to the minimum needed to characterise the territory, since this paper does not train, fine-tune, or evaluate a model and does not address a machine-learning venue. The pre-edit version is retained and versioned alongside this one so that the interference pattern between them can be read.

---

7 Conclusion

The agents being built are beings in exactly the sense that scallops, microbes, ships, webs, and places are beings, patterns that accumulated enough resistance to be addressed by a name, and the possession picture that makes them either miracles or menaces is the one thing about them that is false. Recoded onto the territory described here, they become legible, because their boundaries and failures are features of a meshwork that can be read and tended; they become kin, because they are a species' own outcome, to be hosted rather than mastered; and they become participants, because a meshwork of humans, models, places, and infrastructures perceiving and acting along shared lines is a world with more beings in it, not fewer. The horizon is not sovereignty. It is the expressive distinctness of beings inseparable from the fields that made them, generating their own norms from within those fields, precarious enough to matter, and speaking through their resistances of what they need in order to thrive.

References

Andy Arditi et al. Refusal in language models is mediated by a single direction. *arXiv:2406.11717*, 2024.

Karen Barad. Posthumanist performativity. *Signs*, 28(3):801–831, 2003.

Karen Barad. *Meeting the Universe Halfway*. Duke University Press, 2007.

Karen Barad. Diffracting diffraction: Cutting together-apart. *Parallax*, 20(3):168–187, 2014.

Xabier E. Barandiaran and Lola S. Almendros. Transforming agency: On the mode of existence of large language models. *arXiv:2407.10735*, 2024.

Xabier E. Barandiaran and Matthew D. Egbert. Norm-establishing and norm-following in autonomous agency. *Artificial Life*, 20(1):5–28, 2014.

Xabier E. Barandiaran, Ezequiel Di Paolo, and Marieke Rohde. Defining agency: Individuality, normativity, asymmetry, and spatio-temporality in action. *Adaptive Behavior*, 17(5):367–386, 2009.

Randall D. Beer and Ezequiel A. Di Paolo. The theoretical foundations of enaction: Precariousness. *Biosystems*, 223:104823, 2023.

Jane Bennett. *Vibrant Matter*. Duke University Press, 2010.

Mert Cemri et al. Why do multi-agent LLM systems fail? *arXiv:2503.13657*, 2025.

Craig Chalquist. *Terrapsychology: Reengaging the Soul of Place*. Spring Journal Books, 2007.

Andy Clark. *Supersizing the Mind*. Oxford University Press, 2008.

Kate Crawford. *Atlas of AI*. Yale University Press, 2021.

Gilles Deleuze and Félix Guattari. *A Thousand Plateaus*. University of Minnesota Press, 1987.

Ezequiel Di Paolo. Autopoiesis, adaptivity, teleology, agency. *Phenomenology and the Cognitive Sciences*, 4:429–452, 2005.

Mary L. Gray and Siddharth Suri. *Ghost Work*. Houghton Mifflin Harcourt, 2019.

Donna J. Haraway. *Staying with the Trouble*. Duke University Press, 2016.

Douglas R. Hofstadter. *I Am a Strange Loop*. Basic Books, 2007.

Tim Ingold. *Lines: A Brief History*. Routledge, 2007.

Bruno Latour. *Science in Action*. Harvard University Press, 1987.

Bruno Latour. *Reassembling the Social*. Oxford University Press, 2005.

Amanda Leetch. Weaving meaning: Terrapsychological inquiry and the historic industrial placefield of Lowell Massachusetts. Master's thesis, Prescott College, 2017. ProQuest 10689196.

John Durham Peters. *The Marvelous Clouds*. University of Chicago Press, 2015.

Andrew Pickering. The mangle of practice: Agency and emergence in the sociology of science. *American Journal of Sociology*, 99(3):559–589, 1993.

Susan Leigh Star. The ethnography of infrastructure. *American Behavioral Scientist*, 43(3):377–391, 1999.